

**Borough of Grove City
Grove City Airport
Contract No. 13
Install Perimeter Fencing (Front Gate Entrance)**

Pre-Bid:	Bid Date:	September 15, 2020
Time:	Time:	11:00 AM
Location:	Location:	Borough of Grove City, 123 West Main Street, Grove City, Pennsylvania 16127

PROJECT ENGINEER: Brian R. Wolfel, PE – B.Wolfel@gaiconsultants.com*
CONTACT FOR PLANS: Chelsea Moore, c.moore2@gaiconsultants.com or 814.299.4694

*Direct all technical questions to the project engineer via email.

COMPANY NAME	PHONE	FAX	LOCATION	Apparent Low Bidder and Bid Amount

Revised 8/5/2020 - kjs

Notice and Disclaimer:--The information contained on this page has been compiled from information provided by third parties and/or sources reasonably believed to be reliable and is made available solely for the convenience of those accessing this page for informational purposes only, provided however, the information contained on this page has not been verified or checked. Therefore, no representation, express or implied, is made as to its accuracy, veracity, or usefulness. Any use of or reliance on the information on this page shall be at the sole risk of the user and without liability to or recourse against GAI, its successors or assigns. Any party accessing this information shall be deemed to have understood, agreed to, and accepted the foregoing terms of this **Notice and Disclaimer** as consideration for using any of the information contained hereon.

Project Description

The project will consist of installing new perimeter fencing and gates around the front gate entrance on airport property. Work will include installing chain-link fencing, installing two cantilever chain-link sliding gates, installing electric drive-rail gate operators/card readers/detector loops, demo of existing swing gates and restoring/seeding any disturbed areas.



Below are approximate items and quantities for the base bid:

Item No.	Quantity	Unit	Item Description
SECTION 203	40	CY	CLASS 1 EXCAVATION
SECTION 309	275	SY	SUPERPAVE ASPHALT MIX DESIGN, HMA BASE COURSE – PG 64-22, 0.3<3 MILLION ESAL'S 25.0MM MIX, 4" DEPTH
SECTION 409	275	SY	SUPERPAVE ASPHALT MIX DESIGN, HMA WEARING COURSE – PG 64-22, 0.3<3 MILLION ESAL'S 12.5MM MIX, 2" DEPTH
SECTION 491	195	SY	MILLING OF ASPHALT PAVEMENT SURFACE 6" DEPTH
C-105-6.1	LUMPSUM	LS	MOBILIZATION
F-162-5.1	255	LF	8' CHAIN-LINK FENCE
F-162-5.2	LUMPSUM	LS	PERIMETER FENCE REPAIR AND ACCESS GATES
625.1	2	EA	20' X 8' ELECTRIC SLIDING GATE
S-200-3.1	LUMPSUM	LS	SAFETY REQUIREMENTS

Alternate No. 1: Additional Pavement Section

Item No.	Quantity	Unit	Item Description
SECTION 309	510	SY	SUPERPAVE ASPHALT MIX DESIGN, HMA BASE COURSE – PG 64-22, 0.3<3 MILLION ESAL'S 25.0MM MIX, 4" DEPTH
SECTION 409	510	SY	SUPERPAVE ASPHALT MIX DESIGN, HMA WEARING COURSE – PG 64-22, 0.3<3 MILLION ESAL'S 12.5MM MIX, 2" DEPTH
SECTION 491	510	SY	MILLING OF ASPHALT PAVEMENT SURFACE 6" DEPTH

Alternate #2: Eliminate Southeast Gate and Repair Fence

Item No.	Quantity	Unit	Item Description
F-162-5.3	LUMPSUM	LS	AMOUNT TO BE DEDUCTED TO REPAIR FENCE IN LIEU OF INSTALLING WEST GATE

Alternate #3: Eliminate North Gate and Repair Fence

Item No.	Quantity	Unit	Item Description
F-162-5.4	LUMPSUM	LS	AMOUNT TO BE DEDUCTED TO REPAIR FENCE IN LIEU OF INSTALLING NORTH GATE

