



**Borough of Grove City
Grove City Airport
Contract No. 13
Install Perimeter Fencing (Front Gate Entrance)**

Pre-Bid:	Bid Date:	March 11, 2021
Time:	Time:	11:00 AM
Location:	Location:	Borough of Grove City, 123 West Main Street, Grove City, Pennsylvania 16127

PROJECT ENGINEER: Brian R. Wolfel, PE – B.Wolfel@gaiconsultants.com*
CONTACT FOR PLANS: Kim Sayre, k.sayre@gaiconsultants.com or 412.399.5189

*Direct all technical questions to the project engineer via email.

COMPANY NAME	PHONE	FAX	LOCATION	Apparent Low Bidder and Bid Amount
Hoffman Fence	724.656.9260		New Castle, PA	
Metal Fence Supply	724.530.7212		Slippery Rock, PA	
Penn Fencing Inc.	814.677.7539		Seneca, PA	
Allegheny Fence Construction Company	412.421.6005		Pittsburgh, PA	
Harmon Fence Co.	724.528.4551		Pulaski, PA	
Estherlee Fence Co Inc.	330.549.9863 X103	(330)-549-0053	North Lima, Ohio	
Pennwest Specialized Contracting	724.406.5780		Grove City, PA	
Abel Fence LLC	717.252.2946		Wrightsville, PA	

Revised 3/4/2021 - kjs

Notice and Disclaimer:--The information contained on this page has been compiled from information provided by third parties and/or sources reasonably believed to be reliable and is made available solely for the convenience of those accessing this page for informational purposes only, provided however, the information contained on this page has not been verified or checked. Therefore, no representation, express or implied, is made as to its accuracy, veracity, or usefulness. Any use of or reliance on the information on this page shall be at the sole risk of the user and without liability to or recourse against GAI, its successors or assigns. Any party accessing this information shall be deemed to have understood, agreed to, and accepted the foregoing terms of this **Notice and Disclaimer** as consideration for using any of the information contained hereon.

Project Description

The project will consist of installing new perimeter fencing and gates around the front gate entrance on airport property. Work will include installing chain-link fencing, installing two cantilever chain-link sliding gates, installing electric drive-rail gate operators/card readers/detector loops, demo of existing swing gates and restoring/seeding any disturbed areas.

Below are approximate items and quantities for the base bid:

Item No.	Quantity	Unit	Item Description
SECTION 203	40	CY	CLASS 1 EXCAVATION
SECTION 309	275	SY	SUPERPAVE ASPHALT MIX DESIGN, HMA BASE COURSE – PG 64-22, 0.3<3 MILLION ESAL'S 25.0MM MIX, 4" DEPTH
SECTION 409	275	SY	SUPERPAVE ASPHALT MIX DESIGN, HMA WEARING COURSE – PG 64-22, 0.3<3 MILLION ESAL'S 12.5MM MIX, 2" DEPTH
SECTION 491	195	SY	MILLING OF ASPHALT PAVEMENT SURFACE 6" DEPTH
C-105-6.1	LUMPSUM	LS	MOBILIZATION
F-162-5.1	255	LF	5' CHAIN-LINK FENCE
F-162-5.2	LUMPSUM	LS	PERIMETER FENCE REPAIR
625.1	2	EA	20' X 5' ALUMINUM SLIDING GATE
S-200-3.1	LUMPSUM	LS	SAFETY REQUIREMENTS

Alternate No. 1: Additional Pavement Section

Item No.	Quantity	Unit	Item Description
SECTION 309	510	SY	SUPERPAVE ASPHALT MIX DESIGN, HMA BASE COURSE – PG 64-22, 0.3<3 MILLION ESAL'S 25.0MM MIX, 4" DEPTH
SECTION 409	510	SY	SUPERPAVE ASPHALT MIX DESIGN, HMA WEARING COURSE – PG 64-22, 0.3<3 MILLION ESAL'S 12.5MM MIX, 2" DEPTH
SECTION 491	510	SY	MILLING OF ASPHALT PAVEMENT SURFACE 6" DEPTH

Alternate #2: Install West Gate In Lieu Of Fence Repair

Item No.	Quantity	Unit	Item Description
F-162-5.3	LUMPSUM	LS	INSTALL WEST GATE IN LIEU OF FENCE REPAIR

Alternate #3: Install North Gate In Lieu Of Fence Repair

Item No.	Quantity	Unit	Item Description
F-162-5.4	LUMPSUM	LS	INSTALL NORTH GATE IN LIEU OF FENCE REPAIR

Alternate #4: 8' Chain-link Fence

Item No.	Quantity	Unit	Item Description
F-162-5.5	LUMPSUM	LS	AMOUNT TO BE ADDED TO INSTALL 8' CHAIN-LINK FENCE IN LIEU OF THE 5' CHAIN-LINK FENCE

Alternate #5: 8' Aluminum Sliding Gate

Item No.	Quantity	Unit	Item Description
625.2	LUMPSUM	LS	AMOUNT TO BE ADDED TO INSTALL 8' ALUMINUM SLIDING GATES IN LIEU OF THE 5' ALUMINUM SLIDING GATES

Alternate #6: 5' Electric Sliding Gate

Item No.	Quantity	Unit	Item Description
625.3	LUMPSUM	LS	AMOUNT TO BE ADDED TO INSTALL ITEM 625.3 – 5' ELECTRICAL SLIDING GATE IN LIEU OF ITEM 625.1 - 5' ALUMINUM SLIDING GATES

Alternate #7: 8' Electric Sliding Gate

Item No.	Quantity	Unit	Item Description
625.4	LUMPSUM	LS	AMOUNT TO BE ADDED TO INSTALL ITEM 625.4 – 8' ELECTRICAL SLIDING GATE IN LIEU OF ITEM 625.1 - 5' ALUMINUM SLIDING GATES